	Company Experience					
Sr. Number	Project Name & Nature of Contract	Project Description, Contract Duration & Year of completion	Name of client	Project Cost [VAT EXCLUSISIVE]		
1.	Construction of REA schemes under ADB contract "AFDB/WRKS/18-19/00 6627 for Kassanda, Kyankwanzi, Mubende & Wakiso Districts	130km Bush clarence  Pit excavation, Pole positioning, erection & dressing of 2700 (9m, 12m & 14m) Poles.  Stringing of 125km AAAC 50sqmm HV, 100km of ABCLV conductor  Installation & commissioning of 25 distribution transformers.  Status: Ongoing	STEG International Services Ltd.	UGX 950,000,000		
2.	Refurbishment of Kajjansi & Entebbe Substation	Painting of plant house & guard house, Murram compaction & aggregate surfacing at Entebbe Substation.  Storm water management at Kajjansi Substation Status: Ongoing	Umeme Limited	UGX 157,000,000		
3.	Civil works for Switching Stations	Construction of Switching stations at Kigumba, Lyantonde West, Lyantonde Central & Sironko Completed: November 2021	Umeme Limited	UGX 883,000,000		
4.	Kampala South Kisubi 33kV feeder reliability. "Labour & Transport"	Installation of 3 motorized ABS, three (03) Auto reclosers.  Upgrade of O/H ACSR 50sqmm RL- 11.336km, ACSR50sqmm to 100sqmm RL-0.6km.  Replacement of 303 rotten Poles & Twenty Transformer structures.  Completed: 2021	Umeme Limited	UGX 330,000,000		
5.	Ntami Ivestments Reliability Improvement "Labour & Transport"	Construction of seven 1MVA 33kV TX Plinth.  Installation & Commissioning of seven 1MVA 33kV TXs and associated cable structures  Completed: 2021	Umeme Limited	UGX 126,500,000		
6.	Power Extension to Amosingo, Akabura 1 & Akabura 2 Villages.	Installation & Commissioning of three 50KVA 11Kv TXs  Construction of MV Power line, 11KV, R/L 8.3kM	Umeme Limited	UGX 110,000,000		
	"Labour & Transport"	Completed: October 2021				
7.	Masindi-Alenga 33kV line restoration	Reconstruction of MV line, R/L 7km.	Umeme Limited	UGX 131,000,000		
	"Labour & Transport"	Status: Ongoing				

8.	Civil and Electrical works for the Namanve South UETCL 33kV Lines Integration "Labour & Transport"	Construction of Nine (09) RMU (4 CCC and 5 LCC)  Plinths of concrete class C25.  Design, manufacture, Supply and Installation of 4mx3m fibreglass for nine sites (4 CCC and 5 LCC).  Effective earthing (below 1 ohm) at nine	Umeme Limited	UGX 1,100,000,000
	ARIB	sites using bentonite clay, Safe handling & Transportation from Umeme Lugogo stores, Installation, Testing, Commissioning and cable termination of all the nine RMUs Contract Duration: 6months	International Energy Technik Uganda	56X 150,000,000
9.	Kiriri Substation Power Transformer Upgrade	Completed: <b>December 2020</b> Supply & Installation of all materials necessary to earth the 5MVA 33/11kv Transformer. Earthing of the 5MVA 33/11kV transformer using bentonite clay to achieve 0.2ohms.	Umeme Limited	UGX 142,000,000
	"Labour & Transport"	Safe handling, transportation from Kampala south substation to Kiriri substation, decommissioning of the 2.5MVA 33/11kV, Installation of 5MVA 33/11kV, Heat running, testing & Commissioning of the Transformer. Contract Duration: 1 Months  Completed: 2020		NES
10.	Kamuli Substation Power Transformer Upgrade	Supply & Installation of all materials necessary to earth the 5MVA 33/11kv Transformer.  Earthing of the 5MVA 33/11kV transformer using bentonite clay to achieve 0.2ohms.	Umeme Limited	UGX 325,000,000
	"Labour & Transport"	Safe handling, transportation from Kisubi substation to Kamuli substation, decommissioning of the 2.5MVA 33/11kV, Installation of 5MVA 33/11kV, Heat running, testing & Commissioning of the Transformer.  Construction of a 15/20MVA transformer	*	
		plinth, fitted with a galvanized steel grating, cable trenches and construction of earial earth.  Contract Duration: 3 Months	<b>C</b> >	
11.	Nakawa substation Lines integration	Completed: 2020  Laying 300sqmm 33kV UG cable R/L 1530m, 185sqmm 11kV R/L 350m.  Constructed 11kV OH line, 0.9km.	Umeme Limited	UGX 245,000,000
		Upgraded conductor from ACSR50sqmm to 150sqmm RL 410m Contract Duration: 3 Months Completed: 2020		

12.	REA PROJECT.	CONSTRUCTION OF RURAL	STEG INTERNATIONAL	UGX 1,200,000,000
	Construction of Rural	ELECTRIFICATION SCHEMES	Eng. Abdakhalek.	
	Electrification Schemes	200km Bush clearance		
	Under IDB III for Mpigi,	Pit Excavation, Pole positioning, Erection &		
	Wakiso, Lwengo,	Dressing of 3500 poles i.e., 9m, 12m, and		
	Bukomasimbi and Kiruhura	14meter poles, 2300 Stays		
		Stringing of 65km of AAAC 100mmsq HV		
	/ 30	conductor, Stringing of 130km of AAAC	" (A.	
	/ A *	50mmsq HV conductor	***	1
	/ 2000 /	Installation of 40 Distribution Transformers.		
3				. \
13.	UMEME PROJECT.	Completed: 2019  Excavation of Cable Trenches 1m width x	International Energy Technik	UGX 2,050,000,000
13.	OWEWE PROJECT.		(IET)	UGX 2,050,000,000
1		1.5m depth x 16km length, Coring under marram	(1 - 1)	
7	Kampala Business and	and tarmac road for a total length 318m, 400mm bit/bore		1
1	Industrial	blybore	Eng. Krishna	
I	Park- Namanve (KBIP)	Leving 25kM of 2Core495mmes VLDE Cu 22kV	A STATE OF THE PARTY OF THE PAR	MAY
6.		Laying 25kM of 3Core185mmsq XLPE Cu 33KV Marine Cable.		1
1			The second second	
		Making 100 3Core 33KV Straight Joints	U. A. Shakar	
		Making 25 3Core 33KV outdoor Terminations		0.00
		Making 12 33KV Psfister plug termination and		W/
1		connections to 33KV switchgears.	9	1
1				Property I
4		Construction of 5 H-Pole structures for		* 1
1		connection of 33KV feeders		
1		Testing and commissioning of the 33KV cable	7.	
- N	A. V	system and RMUS.	/ (	7
44	00444444	Completed: 2019	HAMADO AFDIOA	UOD 475 000
14.	20MW Kabulasoke Solar Plant.	Connection of 3400 Modules of 20 panels each to form Strings	IMMODO AFRICA	USD 175,000
				(665,000,000)
	Modules Connection	3600 Trunk cable connections 221 DC Combiner Boxes	Eng. Luis Lires	<i>J</i> .
		DC Wiring for 20km from Combiner Boxes to DC Recombiner at Power station		
		DC Wiring (trunk dc wires) for 73km from modules strings to input of DC Disconnect Box		
		Grounding System for a total length of 15km.	and the second second	
		Communication System of 3km		
		AC Aluminum medium Voltage 36KV for a total		
		of 10km.		
		Electrical Connections of 10 Invertor pads.		
		33KV Switchgear and 1700 MV Electrical		
		Connections Trenches Civil Works of a total length of 5km.		
		Proctor Tests		
		Installation Metro Station Commissioning		
		HV Voltage Cable Testing Hot Spot Testing		
1		60 33KV Indoor/Outdoor Cable Terminations.		1
		Completed 2018		

l i	Engineering of 33KV Concrete Overhead Line.		USD 55,000
Plant, Construction of	Supply and installation of Poles including Civil works	Eng. Luis Lires	(209,000,000)
33Kv Concrete Overhead Line	Supply and Installation of 150mmsq		
	AAAC Conductors, Cross arms, Connectors,	A. \	
	Insulators, Terminations. Installation of Fibre	CZ.	
/ 30	Optics Cable	** Y A	
/ 01	Completed: 2018	· V	
Refurbishment and	Refurbishment and Replacement of Rotten	UMEME	UGX: 71,637,506
Replacement of Rotten	Transformer structures,	Eng. Brian Mwesige 0774-	
Transformer structures		295-779	- \
	Completed 2018	brian.mwesige@umeme.co.ug	
Transformer injections in	Transformer injections in various parts of	UMEME	UGX: 103,981,270
various parts of Uganda, On	Uganda	Eng. Alison Atwiine	
33KV Feeder Lines		0772-720-200,	10.7
	Completed 2017	alison.atwine@umeme.co.ug	
Relocation of Electric Power	Relocation of Electric Power lines in Mbarara	Abubaker Technical Services	UGX:95,000,000
lines in Mbarara Municipality	Municipality 33KV &	and General Supplies limited	111
Laborate Contract Con	11KV Feeders	Wasajja	C/D
Feeders	Completed 2017	Timothy Abubaker	
Relocation of Power line in	Relocation of Power line in Fort Portal	Technical	UGX: 78,200,000
Fort Portal Municipality 11KV	Municipality 11KV Feeder and Transformer	Services and General	
Feeder	structures	Supplies limited	
and Transformer structures		0702-972-450	
A.	Completed: 2017	Wasajja	7
Relocation of Existing Services	Relocation of Existing Services (Powerlines)	China Wu Yi Co Limited P.O.	UGX:180,000,000
(Power lines)	and the state of the	Box 37825	1
7 7 7	A	K'la Uganda	/
	Completed 2017	Sun Qitang	
Transformer injections in	Transformer injections in various parts of	UMEME	UGX: 79,000,000
various parts of Uganda, On	Uganda	Eng. Alison Atwiine	
11KV Feeder lines.		07 <mark>72-720</mark> -200,	
	Completed: 2017	al <mark>iso</mark> natwine@umeme.co.ug	
Power supply to Tatgem	Power supply to Tatgem Uganda Limited (Water	Tatgem Uganda Limited Mr.	UGX: 125,325,910
Uganda Limited (Water & juice	& juice factory).	Tinkamanyire Mugisha 0752-	
factory)		442-240	
	Completed: 2017	sixteendegrees@tatgem.co.ug	
ı	Refurbishment and Replacement of Rotten Transformer structures  Transformer injections in various parts of Uganda, On 33KV Feeder Lines  Relocation of Electric Power lines in Mbarara Municipality 33KV & 11KV Feeders  Relocation of Power line in Fort Portal Municipality 11KV Feeder and Transformer structures  Relocation of Existing Services (Power lines)  Transformer injections in various parts of Uganda, On 11KV Feeder lines.  Power supply to Tatgem Uganda Limited (Water & juice	Supply and installation of 150mmsq AAAC Conductors, Cross arms, Connectors, Insulators, Terminations. Installation of Fibre Optics Cable Completed: 2018  Refurbishment and Replacement of Rotten Transformer structures Completed 2018  Transformer injections in various parts of Uganda, On 33KV Feeder Lines Completed 2017  Relocation of Electric Power lines in Mbarara Municipality 33KV & 11KV Feeders Completed 2017  Relocation of Power line in Fort Portal Municipality 11KV Feeder and Transformer structures Completed: 2017  Relocation of Existing Services (Power lines)  Power supply to Tatgem Uganda Limited (Water & juice factory).	Supply and Installation of 150mmsq AAAC Conductors, Cross arms, Connectors, Insulators, Terminations. Installation of Fibre Optics Cable  Completed: 2018  Refurbishment and Replacement of Rotten Transformer structures  Completed 2018  Transformer structures  Completed 2018  Transformer injections in various parts of Uganda, On 33KV Feeder Lines  Completed 2017  Relocation of Electric Power lines in Mbarara Municipality 33KV & 11KV Feeders Completed 2017  Relocation of Power line in Fort Portal Municipality 11KV Feeders and Transformer structures  Completed: 2017  Relocation of Existing Services Relocation of Existing Services (Power lines)  Relocation of Existing Services (Powerlines)  Relocation of